

INSTRUCTIONS FOR YOUR RADON TEST

1. Close all windows and doors 12 hours prior to the start of your radon test. Please notify your technician if for any reason this has not been done.
2. Keep all windows closed until the test equipment has been picked up.
3. Close all doors behind you when you enter and exit the structure.
4. Do not break or remove any of the certification seals. Your technician at the conclusion of your test will remove seals.
5. Do not use the fireplace during your test.
6. Operate your central heating and air conditioning system normally.
7. Window air conditioners may be operated only if the outside air vent is off.
8. Please consult with our office if you have any parties, open houses, carpet cleaning, painting, repair work, or other inspections scheduled during the test period.
9. Do not touch the test device. It has a motion detector.